SUB-FRONTAGE 5 (EAST)
SPEAKERS' CORNER TO SOUTH PARADE PIER

The concrete stepped revetment and raised promenade that was completed in December 2024 will be continued up to South Parade Pier. The promenade will be raised by around half a metre, with ramped access provided at regular intervals for access to the beach.

Terraced planting will be built on the landward side of the promenade, to manage the level difference with the existing highway and raised defences.

A two-way cycle lane will run along its length, adjacent to the resurfaced highway. Grade II listed light columns will be refurbished and new lighting and seating installed.

At South Parade Pier, improvements will be made under the canopy area, with a resin bound gravel surface laid, replacing the deteriorating surface. The existing ramps will also be encased with a warm white concrete and the handrails replaced.